

EO TYPE III (for distribution of *GES* packages)

DISTRIBUTION BY:

ENGINEERING DOCUMENTATION

☐ INITIATOR OR OTHER

TYPE OF PACKAGE

TYPE OF FUNDING (check one)

WORK PERFORMED BY (check one)

☐ REVIEW
☒ FINAL

☐ AUTHORIZATION JOB (EJO)
☒ WORK ORDER (WCF)
☐ OTHER

☐ MAINTENANCE
☒ ON-SITE CONTRACTOR
☐ OTHER CONTRACTOR
☐ N/A

DISTRIBUTION:

Name / Organization	Bldg.	# of Copies
*D. Warfield - FQE (information only)	T130D	1
MARK AUSTIN ERE PROJECT	080	1
JEFF FAUBLE ERE ENG	130	1
BOB CAMPBELL ERE ENG	130	1
STEVE HOWARD DOE	T124A	1
SCOTT SUROVCHAK	T117A	1
DICK NORTON RADENG	T140B	1
BRIAN HASENACK ^{SPKR} CONST. MGMT	080	1
JEFF SIMMS, CONST MGMT	T750A	1
T. KRAMER, PM	030	1
RICK DUNN, OPERATIONS	774	1
M MCKEE, SOLAR FONDS	080	1
T. DANIELSON, SPRP	080	1
KEITH FARLEY HIS	130	1
BRUCE CAMPBELL F.P.	130	1
KYLE PETER, RCRA COMP.		1
LINDA EHRLICH, ARCH	130	1

REMARKS SECTION

(Attached documents are as listed on the Document Index)

A TABLETOP REVIEW MEETING HAS BEEN SCHEDULED

ON _____ AT _____ AM PM

IN ROOM _____ IN BUILDING _____

PROJECT/WCF NUMBER

BLDG:

TITLE:

989 884

964

BUILDING 964 REMOVAL

INITIATOR (Print, Sign)

LINDA EHRLICH

DATE _____

12/1/94

EXT.

7949

EO COORDINATOR (Print, Sign)

DONNA STRATTON

DATE _____

12/01/94

EXT

5092

EO #

37056 GES001

REF. EO #

EO DISTRIBUTION DATE

12-1-94

ED CHARGE NUMBER

REVIEWED FOR CLASSIFICATION/UCNI

* Distribution to FQE is only mandatory for Final Type III EOs. The Initiator may cross out FQE on Review Type I, II, or III EOs.

DES-253/4-1(1) 03/07/94

ADMIN RECORD

IA-A-000742

Date 12.1.99 2045



000064272

(08/15/94)

APPENDIX 6

Page 1 of 1

GES SCREEN

Job#: 989884Bldg. 964Title: BUILDING 964 REMOVAL

Description: _____

SECTION A - NUCLEAR WORK PROCESS REQUIRED

	Y	N
1. Does work affect/modify Vital Safety Systems	—	X
a. Modify VSS hardware, software or require a change in VSS?	—	X
b. Impact a vital safety function during installation, modification, or repair?	—	X
c. Will this work create a "Violation" with respect to any Criticality Safety Operating Limit (CSOL) or Nuclear Material Safety Limit (NMSL), or is a new CSOL or NMSL required?	—	X
d. Will this work require any modification, addition or deletion of an existing VSS procedure?	—	X
e. Will this work impact any system for which credit is taken in an Operational Safety Requirement (OSR)?	—	X
f. Will this work create an "Out-of-Tolerance" with respect to an OSR Limiting Condition of Operation (LCO)?	—	X
2. Does work involve Hazardous Chemicals of sufficient quantity and/or type to pose potential for catastrophic events? (If applicable, refer to COEM, Section 6.3.6, Appendix 6).	—	X

SECTION B - SAFEGUARDS AND SECURITY SYSTEMS

1. Does work affect Safeguards and Security Systems:	—	X
--	---	---

SECTION C - ENGINEERING SUPPORT PROGRAM (ESP) ELIGIBILITY

If the answer to any of the above questions is "yes," then this modification does not qualify for GES. If all answers are "no," use GES program. Tasks "failing" the screen may still use GES program, if Appendix 7 and Section 6.4 for the EDMPP development is approved by E&SS management.

1. Work is assigned to: GES program

LINDA EHRLICH *Linda Ehrlich* 11/29/94
Preparing Engineer Date

SYSTEM CLASSIFICATION FORM

WORK CONTROL NO. 989884 TITLE: BUILDING 964 REMOVAL

System Name: NONE

Bldg.: 964 Location: EAST OF POND 207B CENTRAL

6.1.1 SYSTEM REFERENCE DOCUMENTS:
NONE

6.1.2 SYSTEM FUNCTIONS AND OPERATING MODES
NOT APPLICABLE

6.2 SYSTEM CLASSIFICATION (Identify references from those documents listed in Section 6.1.1 and enter technical justification on appropriate space below).

Category ☐ 1 ☐ 2 ☐ 3 ☒ 4

Basis:

THE BUILDING DOES NOT MEET THE REQUIREMENTS OF SYSTEMS CATEGORY 1 OR 2. IT IS NOT RELIED UPON FOR WORKER PROTECTION FROM RADIOLOGICAL OR TOXIC HAZARDS. IT IS NOT REQUIRED FOR PROTECTION OF SNM, CLASSIFIED MATERIAL OR SITE RESPONSE EMERGENCY. THE BUILDING DOES NOT HAVE A FIRE SPRINKLER SYSTEM. THIS BUILDING IS A SYSTEM CATEGORY 4.

LINDA EHRLICH
Cognizant Engineer

Linda Ehrlich X7949
Print Name Cognizant Engineer Signature Ext/DP

10/27/94
Date

ENGINEERING WORK PLAN

FOR

BUILDING 964 REMOVAL

OCTOBER 1994

Mark Austin
Project Engineer

DESIGN INPUT

5

CONCURRENCE SHEET

TE Kramer
T. Kramer, Work Package Manager / Project Manager

10-11-94
Date

M. R. Austin
M. R. Austin, Project Engineer

10/11/94
Date

J. Fauble, ER Design Engineering

Date

Revision Record

Rev #	Purpose	Date	Approval(s)
0	Original Issue	10-10-94	

1.0 Project Identification

The purpose of this project is to remove Building 964 to allow for the IM/IRA Phase I closure of the Solar Evaporation Ponds. The building is located east of 207B Center pond and consists of a wood frame structure covered with galvanized steel siding and a rolled asphalt roof. The building is used as a RCRA storage facility and does not have a history of contamination concerns.

2.0 Project Budget and Cost Plan

The project cost, based from the rough order of magnitude cost estimate from Tom Danielson in *AUGUST 1994*, is \$2,000,000. At the time, only limited information about the facility was available, and the scope estimate from Building 788 was used to develop the ROM number. Engineering & Project Management has prepared a scope level document and has proposed 80 hours to complete a General Engineering Services Title II package to remove the facility.

4.0 Project Justification

This project is required to allow for the optimization of the OU-4 Phase I IM/IRA.

5.0 Assumptions and Basis of Estimate

The engineering BOE's for Title II Design were provided by the engineering disciplines required for the project. The design hour commitments are listed below for Title II Activities:

Project Engineer	10	hours
Architectural Engineering	80	hours

Assumptions made consist of the following:

1. Relocation of the wastes (approximately 2092 drums) were not included in the scope.
2. The building was assumed to be "clean" from a radiological perspective and could be removed without special contamination concerns. Dick Norton of Rad Engineering stated that no rad concerns presently exist on the facility.
3. The building would be removed and disposed of as scrap material or wastes the landfill can take.
4. Rad./Haz. Monitoring will be required before anything can be released from the PA.

6.0 Relationship to Other Projects

This project is related to the OU-4 Phase I IM/IRA closure action. This building is to be removed prior to initiating the Phase I work.

7.0 Key Personnel and Responsibilities

Project Manager (PM) : T. Kramer


The PM is responsible for all DOE and 4700.1 reporting requirements for the project, work package development and maintenance, and provides the authorization to the Project Engineer to perform the design work for the project. The PM reports to the Program Manager for OU-4.

Project Engineer (PE): M. R. Austin

The PE is responsible for the technical baseline of the project and ensuring the design meets the needs of the PM. The PE is also responsible for coordination of the support disciplines, ensuring schedule and cost commitments for engineering activities are met, compilation of all support discipline deliverables to combine it into one completed Title design package, providing plantwide review of design packages, ensuring compliance with DOE 6430.1A, COEM and RFP Standards. The PE reports directly to the PM.

Architectural Engineer: L. Ehrlich

The architectural discipline engineer is responsible for providing a General Engineering Services (GES) design package which meets the needs identified in the scope document. The design should be in accordance with good engineering practices and meet all applicable requirements. The discipline engineer provides, as a deliverable to the PE, their completed drawings and specifications which meet the applicable design requirements. The discipline engineer is responsible for resolution of comments received from reviewers of the design package and receiving approvals required by their design managers.



Organizational Breakdown Structure

9.0 Schedule Requirements

(See Next Page)

Name	Earliest Start	Earliest Finish	Duration	% Done
964 Scope Approval	10/11/94	10/11/94	1	0
Issue ESR & Approval of	10/12/94	10/12/94	1	0
Issue DSR to Architectural	10/13/94	10/13/94	1	0
Photo Shoot of Building	10/14/94	10/27/94	10	0
GES Design of 964	10/26/94	11/1/94	5	0
Prepare 964 for GES	11/2/94	11/2/94	1	0
Printing / Distribution of	11/3/94	11/7/94	3	0
964 Package Review	11/8/94	11/18/94	9	0
964 Review Meeting	11/21/94	11/21/94	1	0
964 Comment / Response	11/22/94	11/24/94	3	0
964 Final Package	11/25/94	11/25/94	1	0
Schedule Reserve	11/28/94	12/1/94	4	0
964 GES Package Approval	12/2/94	12/2/94	1	0
Print / Distribute Final	12/5/94	12/7/94	3	0

10/11/94

Building 964 Removal - EWP Schedule

10

8

9/5/94	9/19/94	10/3/94	10/17/94	10/31/94	11/14/94	11/28/94	12/12/94	12/26/94
	Issue ESR & Approval of Eng. Work Plan	964 Scope Approval						
	Issue DSR to Architectural Engineering							
	Photo Shoot of Building 964							
		GES Design of 964 removal						
		Prepare 964 for GES Review						
		Printing / Distribution of 964 Package						
			964 Package Review					
			964 Review Meeting					
			964 Comment / Response					
			964 Final Package Configuration					
			Schedule Reserve					
			964 GES Package Approval					
			Print / Distribute Final 964 Package					


10/11/94

Building 964 Removal - EWP Schedule

12

10/11/94

Building 964 Removal - EWP Schedule



11

**TECHNICAL SCOPE
&
CONSTRUCTION SPECIFICATIONS
for
BUILDING 964 REMOVAL**

Prepared by:

**EG&G ROCKY FLATS, INC.
Engineering and Technology
Rocky Flats Plant
Golden, Colorado**

Project No. 989884

December 1, 1994

SECTION 01006-DRAWING LIST

This is a list of the drawings:

<u>DRAWING No.</u>	<u>REV. No.</u>	<u>TITLE</u>
30000-001	AC	AREA PLOT PLAN
37805-13-01A	A	BUILDING 964 REMOVAL

SECTION 02050- DEMOLITION TECHNICAL SCOPE

PART I GENERAL

1. The building was constructed around 1966 to 1969. The exterior is galvanized steel siding with approximately four feet of corrugated fiberglass around the top. The roof of the building is rolled asphalt roofing system. The building has four sliding doors located on the south face of the building. The doors are supported from and move along a track above the door. The foundation is a thickened concrete slab, this is to remain in place and be disposed of by others. The support structure of the building is heavy timber post and beam framing. There are wood girts spanning between exterior columns which support the exterior siding and corrugated fiberglass. The roof is supported by wood roof trusses. There is one line of interior columns located at the center of the building. The building structure and siding is anticipated to be free released.
2. All equipment and materials within the building will be relocated by others, the building is currently being used to store low level waste. There is also a desk, chairs, miscellaneous tools, a storage cabinet and a spill kit cabinet inside of the building.
3. There are no known contamination concerns with the building or floor slab. The possibility of RCRA spills from the stored waste on the floor slab does exist.
4. All items either removed from the building or rubble from the demolition of the building shall be monitored for radioactive contamination and Hazardous Waste contamination. No building or structure contamination concerns are expected.
5. The roofing material also needs to be inspected for possible asbestos. Industrial Hygiene shall inspect roofing debris for possible asbestos.
6. All work shall be done in accordance with Rocky Flats Health & Safety Practice Manuals.

PART II ARCHITECTURAL

1. Before demolition of building 964 all waste storage drums, wood pallets and miscellaneous items shall be removed from the interior of the building by others.
2. Demolish building 964 down to the concrete floor slab. This includes but is not limited to removing siding, corrugated fiber glass panels, roofing, girts, purlins and timber support structure.
3. Cut all protruding anchor bolts flush with the top of the concrete floor slab.
4. Location of a temporary laydown and sorting area shall be decided by Construction Management.
5. See Selective Demolition Specification for general requirements.

PART III PIPING/MECHANICAL

1. There are no mechanical systems in the structure therefore no work is required.

PART IV ELECTRICAL

1. There are no electrical systems in the structure therefore no work is required.

PART V FIRE PROTECTION

1. There are no fire protection systems in the structure therefore no work is required.

SECTION 02070-SELECTIVE DEMOLITION

PART I GENERAL

1.1 WORK INCLUDED

- A. Provide all labor, materials, tools and equipment necessary for, or incidental, to the execution of all demolition as shown on the contract drawings and as specified herein in accordance with the provisions of the Contract Documents and completely coordinated with the work of all other trades. Although such work is not specifically shown or specified, all supplementary or miscellaneous items, appurtenances and devices incidental to or necessary for a sound secure and complete demolition shall be furnished and installed as part of this work.
- B. Work includes the removal of items indicated on the contract demolition drawings.
- C. Submittal-Ten days prior to start of the work, submit a demolition schedule for approval that outlines proposed demolition start dates and durations. Demolition of existing facilities shall be in accordance with the approved demolition schedule. Changes to the approved schedule shall be subject to approval by the Contractor.
- D. All work shall be performed in accordance with NFPA 241, Standard for Construction, Alteration and Demolition Operations.
- E. Any cutting or welding operations shall require a "Hot Work Permit" from the Fire Prevention Bureau (T371F).
- F. All work shall be performed in accordance with HSP 12.11.

PART II PRODUCTS


- 2.1 EQUIPMENT: Equipment used in any demolition work must be equipped with safety devices that will adequately protect the operator.

PART III EXECUTION


- 3.1 PROTECTION OF EXISTING WORK: Before beginning any cutting or demolition work, carefully survey the existing work and examine the drawings and specifications to determine the extent of the work. Take all necessary precautions to ensure against damage to existing work to remain in space, to be reused or to remain the property of the Contractor, and any damage to such work shall be repaired or replaced as approved by Contractor at no additional cost to the Contractor. Carefully coordinate the work of this section with all other work.
- 3.2 DUST CONTROL: Not applicable.
- 3.3 BURNING: The use of burning at the project site for the disposal of refuse and debris will not be permitted.
- 3.4 SALVAGE: Removed materials designated for salvage shall be stored in areas on the Rocky Flats plantsite designated by the Contractor. All such material shall remain the property of the Contractor.

- 3.5 **DISPOSAL:** All materials not designated for reuse or salvage shall be removed from the jobsite. Disposal of these materials shall be made at a dump site on the Rocky Flats plantsite designated by the Contractor.


END OF SECTION



FLOOR PLAN - BLDG 964
SCALE: 1/16" = 1'-0"



SOUTH ELEVATION
SCALE: 1/16" = 1'-0"



SIDE ELEVATION
SCALE: 1/16" = 1'-0"

NOTES

1. Demolish building 964 down to the concrete floor.
2. Cut all protruding anchor bolts flush with the top of the concrete floor.
3. The subcontractor shall prepare and submit a sequence of work, crating plan and hoisting/ rigging plan for engineering approval.
4. All items removed from or generated from the demolition work shall be monitored and cleared by Radiological Engineering before removal from the protected area. Then disposition items for reuse or recycling as is appropriate.
5. Industrial Hygiene shall inspect roofing debris for possible asbestos. The debris shall then be sorted and disposed of as is appropriate.
6. Work this drawing with demolition description of work. See Section 02050-Demolition Technical Scope and 02070-Selective Demolition Specification for general requirements.

INTERIM DRAWING - CONSTRUCTION ONLY

AS-BUILT MASTER DRAWING WHEN CONSTRUCTION IS COMPLETE

RESPONSIBLE GROUP

1A	INTERIM ISSUE	12/1/94	RP	989884	
ISSUE	DESCRIPTION	DATE	REP	DOE	CLASS
DESIGNED - EARLICH	BLDG. 964				
DRAWN - EARLICH	REMOVAL				
CHECKED - Mott	BUILDING FLOOR PLAN				
APPROVED - Campbell	E-ELEVATIONS				
RELEASE DATE					
Rocky Flats Plant					BLDG. 964
GOLDEN, COLORADO					ROOM
SIZE		ISSUE	SHEET		CAT.
B	37805-13-01A	A	1 of 1		L